

TARCO® Highlander Model HL-HY2 Ice & Snow Control Hopper Spreaders: Powered From Truck Hydraulics

BASIC DESCRIPTION: 10 gauge hot roll steel (A36) or 10 gauge type 304 stainless steel hopper construction; four (4) lifting eyes; 50:1 gear box with 5.4 White Hydraulic Motor (U.S. Made); 24" wide conveyor chain with 3/8" x 1-1/2" bar flights (U.S. Made); jack controlled discharge gate; wear plate 3/16" thick; fully enclosed tip-up spinner assembly with two (2) internal baffles; four (4) material deflectors; H.D.G heavy duty top screens (shipped loose); four (4) dump body hold downs (shipped loose); hydraulic conveyor & bottom mounted Char-Lynn spinner motor (U.S. Made); stainless steel light bar (shipped loose), (2 red stop/tail/turn, 3 light red cluster, 2 amber flasher lights, and 2 white spot lights) 20" dia. poly spinner disc, steel spreader painted - TARCO® Yellow OR Omaha Orange, stainless steel spreaders are left unpainted.

Hydraulic Requirements: (HY2) – 20 GPM @ 1800 PSI

Hopper Construction: 10 Gauge Hot Roll Steel (A36)

Model	Length	LIST PRICE FOB Factory		
HL-HY2-8 HR	8 ft.	\$17,563.00		
HL-HY2-9 HR	9 ft.	\$17,878.00		
HL-HY2-10 HR	10 ft.	\$18,198.00		
HL-HY2-11 HR	11 ft.	\$18,524.80		
HL-HY2-12 HR	12 ft.	\$19,23.40		
HL-HY2-13 HR	13 ft.	\$20,641.60		
HL-HY2-14 HR	14 ft.	\$22,044.40		
HL-HY2-15 HR	15 ft.	\$22,909.60		
HL-HY2-16 HR	16 ft.	\$23,711.80		
HL-HY2-17 HR	17 ft.	\$24,658.20		
HL-HY2-18 HR	18 ft.	\$25,772.60		
HL-HY2-19-HR	19 ft.	\$26,889.80		
HL-HY2-20-HR	20 ft.	\$27,704.60		

Hopper Construction: 10 Gauge Type 304 Stainless Steel (2B Finish)

Model	Length	LIST PRICE FOB Factory		
HL-HY2-8 SS	8 ft.	\$20,786.20		
HL-HY2-9 SS	9 ft.	\$21,690.20		
HL-HY2-10 SS	10 ft.	\$22,612.80		
HL-HY2-11 SS	11 ft.	\$23,538.20		
HL-HY2-12 SS	12 ft.	\$25,463.20		
HL-HY2-13 SS	13 ft.	\$26,336.80		
HL-HY2-14 SS	14 ft.	\$27,206.20		
HL-HY2-15 SS	15 ft.	\$28,078.40		
HL-HY2-16 SS	16 ft.	\$28,946.40		
HL-HY2-17 SS	17 ft.	\$29,813.00		
HL-HY2-18 SS	18 ft.	\$30,882.60		
HL-HY2-19-SS	19 ft.	\$31,955.00		
HL-HY2-20-SS	20 ft.	\$33,026.00		

LIST PRICE FOB Greenwich, NY. HL-HY2-5/2022



Options:

Part Number		LIST PRICE
CMH	Chassis Mounting Hardware (stabilizer kit OR spring loaded)	\$595.00*
6EXTHR	2", 4" OR 6" Built-in hopper extension (HR)	\$764.40
12EXTHR	8", 10", OR 12" Built-in hopper extension (HR)	\$1,072.40
6EXT SS	2", 4" OR 6" Built-in hopper extension (SS)	
		\$1,505.00
12EXTSS	8", 10", OR 12" Built-in hopper extension (SS)	\$2,849.00
EXTIDL	Extended Idler Take-up rods for front idler bearings	\$218.40
EXTGRE	Extended Grease Lines for front idler bearings	\$189.00
ESHR	Front OR Rear Economy Deflector (45 Degree – HR)	\$148.40*
ESSS	Front OR Rear Economy Deflector (45 Degree – SS)	\$624.40*
CSHR	Cab Shield, 24" (HR)	\$415.80*
CSSS	Cab Shield, 24" (SS)	\$1,101.80*
SPAPR	Hopper Spill Aprons w/ keepers (belting, not installed)	\$439.60*
CATHR	Catwalks, diamond plate steel (painted black)	\$582.40*
CATALUM	Catwalks, diamond plate aluminum	\$999.60*
CATSS	Catwalks, stainless steel with grip tape	\$2,020.20*
POLYWR	³ / ₄ " Thick Poly Wear Plate in lieu of HR or SS	\$708.40
HRTOP	HR Angle welded to top perimeter of hopper	\$180.60
SSTOP	SS Angle welded to top perimeter of hopper	\$330.40
HL34	HD HL-34 Side Supports in lieu of standard side gussets	\$1,432.20
EXXM	Extend Cross Members to support liquid tanks (80" OAW)	\$70.00
FLSS	Fork Lift Sockets (SS)	\$1,470.00
FLLSS11	Fork Lift Sockets (SS) (12' and up)	\$1,911.00
LDHR	Ladder (HR) (painted black)	\$273.00*
LDSS	Ladder (SS)	\$550.20*
GRDSPD	Speed Sensor for White Hydraulic Motor (4 Pin)	\$420.00
CHEV10	Chevron Conveyor Chain in lieu of Std. (9 ft., 10 ft., 11 ft.)	\$455.00
CHEV12	Chevron Conveyor Chain in lieu of Std. (12 ft., 13 ft., 14 ft.)	\$604.80
VEEHR	Conveyor Bridge (HR) (Std. on 12, 13, 14 ft. units)	\$256.20
VEESS	Conveyor Bridge (SS) (Std. on 12, 13, 14 ft. units)	\$513.80
TMSPIN	Top Mounted Spinner Motor with Drive Shaft OR Direct Top Mount	\$212.80
HLGHY2	Gas/Hydraulic Drive with 23 HP Briggs/Stratton Engine OR	\$7,137.20
	20 HP Honda with Battery, Hydraulic Pump	•
GB25	25:1 Gear Box in lieu of 50:1 Gear Box	\$330.40
TGLHR	Tailgate Locking Bar HR	\$189.00*
TGLSS	Tailgate Locking Bar SS	\$378.00*
LEDBAR	LED Lighting in lieu of Incandescent, for Standard Light Bar	\$294.00
HY3	Dual Hydraulic Motors drive in lieu of Gearbox 56:1 (HY3)	\$1,226.40
DUALSPN	Dual Spinner Assembly (14" dia. poly discs)	\$1,248.80
DUALKNB	Dual Knob Spreader Valve w/ Pedestal	\$330.40*
PIPE2FRNTHR	HR Hard Pipe to Front of Spreader with hoses (A31605-1)	\$221.20
PIPE2FRNTSS	SS Hard Pipe to Front of Spreader with hoses (A31605-2)	\$513.80
TSINSTALL	Top Screens Factory Installed	\$490.00
LBINSTALL	Light Bar Factory Installed	\$252.00
BIG SCOTTIE	Auger Drive in lieu of Conveyor Chain Drive	No Charge
210 00011111	Tage 2.110 in new of conveyor chain billio	1.0 Charge

(*) – Shipped loose, not installed

Deducts

No Top Screens – Deduct \$350.00 No Light Bar – Deduct \$350.00 No Dump Body Hold-Down Equipment – Deduct \$125.00 No Hoses or Quick Couplers – Deduct \$125.00 LIST PRICE FOB Greenwich, NY HL-HY2-5/2022